

Hachi Infinite M1 Pro

HACHI INFINITE M1 PRO



The Infinite M1 Pro DLP projector from Hachi has 600 Ansi lumens, a contrast of 600:1 and an HDTV 1280 x 720 resolution. With a projection ratio of just 0.39:1, this projector never gets in the way. For a 2m wide image, the projector only needs to be 78 cm away from the screen. As the projector recognizes DLNA, Airplay and Miracast screen mirroring signals, it is possible to play videos with high resolution and surround sound directly via WLAN from a smartphone, tablet or PC (Android, Windows and iOS). Even 1080P playback is no problem for the projector. At just 30 decibels, the device is one of the quieter projectors. The model was built by Hachi in 2020 and is no longer current.

Brief Introduction

Beta 2.5

Display Type

1 x DLP Chip
HDTV 16/9 Ti Digital Light Processing Chip

Ansi-Lumen

600

267 Lux (bei 200 cm Screen)

Contrast

600:1

600:1

Black Level

1,0000 min. Lumen

0,447 min. Lumen

Offset

Resolution

HDTV 1280 x 720

921.600 Pixel

HDTV 1920 x 1080 compressed

Video Modes

Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, EDTV 480p, 576p

Disc Recognition

DVD | HD Blu-ray (komprimiert) | 3D-Blu-ray | 4K-UHD-Blu-ray

Application

Short Distance | Small screen width, rooms with very little ambient light below 100 lumens.

Light Source

-

Light Life

-

Operating Costs

-

Focus

Automatic

Zoom

No Zoom

Objective

-

Throw Ratio

0,39:1

Audio

2 x 5W Full frequency 36mm

Connections


1x HDMI 1.4

1x DisplayPort 1.4

1x USB-C

1x 3,5mm headphone jack





Ceiling Mounting	Yes
Power	30-56W
Size WxHxD	138 x 80 x 215 mm (5,4"x3,1"x8,5") 2,37 L/dm³
Operating Noise	30dB

Weight	1,30 kg / 2,2 lbs.
Keystone	-
Illumination	-

Frequenz	-
----------	---

Foot-Lamberts	25 fL / max. 249 cm screen width 86 cd/m²
---------------	--

- | | |
|----------|---|
| Features | <ul style="list-style-type: none">■ Full HD 1080P compatible■ High Dynamic Range (HDR)■ Wi-Fi network compatible.■ Short-throw projector■ Interactive touchscreen projector■ 10-Point AnyTouch■ CPU Qualcomm Snapdragon SDA670■ RAM 6GB■ Built-in storage: 128GB eMMC■ Bluetooth |
|----------|---|

Status Data	2020 Discontinued (EOL) // Last update of the data: 2023-10-17
-------------	--

More Details



HCinema

<https://www.projector-database.com/pro/HachiinfiniteM1pro-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.