

Acer K137i

ACER K137i



The Acer K137i 3D LED DLP projector has 700 Ansi lumens, a contrast of 10000:1 and a WXGA 1280 x 800 resolution. The manufacturer specifies an LED service life of 30,000 hours, which converts to over 20.5 years at 4 hours of use. An image width of up to 269 cm is possible as the projector has 700 Ansi lumens. However, if room light is available, the picture should be max. 179 cm wide. A smartphone with MHL connection can be connected directly to the MHL/HDMI port and transmit a 1080p / 60 Hz image mirroring (screen mirroring) while the smartphone is being charged at the same time. The model is also Full HD 1080P compatible. The model was built by Acer in 2015 and is no longer current, but is still a popular projector in our database.

Brief Introduction Beta 2.5

Display Type

1 x 0,45" DLP Chip
WXGA 16/10 Ti Digital Light Processing Chip

Ansi-Lumen

700 / 560 im Eco Mode

272 Lux (bei 203 cm Screen)

Contrast

10000:1 full on/off

10000:1 full on/off

Black Level

0,0700 min. Lumen

0.027 min. Lumen

Offset

Resolution

WXGA 1280 x 800

1.024.000 Pixel

HDTV 1920 x 1080 compressed

Video Modes

Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p EDTV 480p, 576p

3D Compatibility

Frame Sequential (3D Ready)

Application

Micro-Portabel | Small mobile presentations..

Small screen width, rooms with very little ambient light below 100 lumens.

Light Source

RGB LEDs

Light Life

30000 h.

Operating Costs

0,00 € LED

Focus

Manual

Zoom

No Zoom

Objective

F=2,0 f=14,95mm

Throw Ratio

1,50:1

Audio

2 x 3W

Connections

HDMI mit MHL in

USB Typ B

Micro SD Card

Mini Jack Audio in und out





Ceiling Mounting
Power
Size WxHxD
Operating Noise

Yes
90W
189 x 41 x 116 mm (7,4"x1,6"x4,6") 0,9 L/dm³
31 / 29 dB in Eco Mode

Weight
Keystone
Illumination

0,510 kg / 0 lbs.
Vert.: +/-40° automatisch
90%

Frequenz

H-sync: 30-100 kHz
V-sync: 50-120 Hz

Foot-Lamberts


25 fL / max. 269 cm screen width
86 cd/m²

- Full HD 1080P compatible
- Eco Mode
- Automatic and manual vertical keystone correction
- Wi-Fi network compatible.
- Crestron®-Software compatible.
- Micro SD Card
- SRS WOW HD Sound
- Incl. enclosed Acer Wireless Dongle
- Screen Mirroring

Status

2015 Discontinued (EOL) // Last update of the data: 2024-10-02
Created: 2015-01-19 11:01:15

Data



More Details



HCinema

<https://www.projector-database.com/pro/acerk137i-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.