

Acer X1211H



ACER X1211H



Brief Introduction

Beta 2.5

A brief introduction to the Acer X1211H. The DLP projector has an XGA 1024 x 768 resolution and a contrast of 1000:1. The lamp life is specified by the manufacturer as 5000 hours, which converts to over 6.8 years at 2 hours per day. 453 cm image width, the projector will be able to illuminate well. However, if room light is available, the picture width should ideally not exceed 302 cm. Furthermore, the projector can play 1080P without any problems. The model was built by Acer in 2011 and is no longer current.



1 x DLP Chip
XGA 4/3 Ti Digital Light Processing Chip

Display Type

Ansi-Lumen
Contrast
Black Level
Offset

2700 / 2160
1000:1 full on/off
2,7000 min. Lumen
900 Lux (bei 200 cm Screen)
1000:1 full on/off
0,903 min. Lumen

Resolution

XGA 1024 x 768
786.432 Pixel
UXGA 1600 x 1200 compressed
PAL, SECAM, NTSC, HDTV 720p, 1080i, 1080p EDTV 480p, 576p

Video Modes

3D Compatibility

Frame Sequential (3D Ready)
Standard-Portabel | External training and company presentations, as well as product presentations.
Medium screen width or rooms with little light, max. 100 lumens.

Application

Light Source

Articel Nr.: EC.JCQ00.001

Light Life

5000 h.

Operating Costs

-

Focus

Manual

Zoom

Manual 1,1

Objective

F=2,56-2,8 f=21,00-23,00 mm

Throw Ratio


1,86-2,04:1

Audio

1 x 10W

Connections

HDMI 1.3 in
2 x D-sub 15 pin in 1 x out
S-Video in
Cinch Video in
Mini Jack Audio in und out



Ceiling Mounting

Yes

Power

287W

Size WxHxD

280 x 84 x 230 mm (11"x3,3"x9,1") 5,41 L/dm³

Operating Noise


-

Weight

2,60 kg / 5,73 lbs.

Keystone

Vert.: +/-40°



Illumination	85%	
Frequenz	H-sync: 31-99 kHz V-sync: 48-120 Hz	
Foot-Lamberts	84 fL / max. 453 cm screen width 288 cd/m²	
Features	■ Full HD 1080P compatible	
Status Data	- 2011 Discontinued (EOL) // Last update of the data: 2023-08-04	

More Details



HCinema

<https://www.projector-database.com/pro/acerx1211h-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.