

Benq TS537

BENQ TS537



With the TS537, manufacturer Benq offers a DLP projector with SVGA 800 x 600 resolution and a contrast of 13000:1. The lamp life is specified by the manufacturer as 4500 hours, which is over 6.2 years with two hours of use per day. A picture width of up to 477 cm is possible. However, the picture should be smaller in room light. We recommend max. 318 cm. It is also Full HD 1080P and 3D compatible. The model was built by Benq in 2013 and is no longer current.

Brief Introduction

Beta 2.5

Display Type

1 x DLP Chip
SVGA 4/3 Ti Digital Light Processing Chip

Ansi-Lumen

3000 1000 Lux (bei 200 cm Screen)

Contrast

13000:1 full on/off 13000:1 full on/off

Black Level

0,2308 min. Lumen 0,077 min. Lumen

Offset

Resolution

SVGA 800 x 600

480.000 Pixel

Video Modes

UXGA 1600 x 1200 compressed

Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, 3D, EDTV 480p, 576p

3D Compatibility

Frame-Packing (Full HD 3D) | Side-by-Side | Top-and-Bottom

Frame Sequential (3D Ready)

Application

Standard-Portabel | External training and company presentations, as well as product presentations.

Light Source

Medium screen width or rooms with a little more ambient light, max. 200 lumens.

Light Life

190W Lamp

Articel Nr.: 5J.J9R05.001

Operating Costs

4500 h. 6500 h. in Eco Mode

9,52% / 0,04 €

Focus

Manual

Zoom

Manual 1,1

Objective

F=2,56-2,8 f=21-23,10 mm

Throw Ratio

1,86-2,04:1

Audio

1 x 2W

Connections

HDMI in

2 x D-sub 15pin in 1 x out


Cinch Video in

Cinch Stereo in

S-Video in

Mini Jack Audio in und out

USB Typ B in



RS232C Din 9 pin in



Ceiling Mounting	Yes
Power	270 / 220W in Eco Mode
Size WxHxD	283 x 88,7 x 222 mm (11,1"x3,5"x8,7") 5,53 L/dm³
Operating Noise	-

Weight	1,90 kg / 4,19 lbs.
Keystone	Vert.: +/-40°
Illumination	-

Frequenz	H-sync: 15-102 kHz V-sync: 23-120 Hz
----------	-----------------------------------------

Foot-Lamberts	93 fL / max. 477 cm screen width 319 cd/m²
---------------	-----------------------------------------------

Features	■ Real Full HD 3D ■ Full HD 1080P compatible ■ Eco Mode ■ Kensington Slot ■ sRGB
----------	----------------------------------------------------------------------------------------------

Optional	Remote control original Lamp original	5J.J9V06.001 / RCX022 5J.J9R05.001
----------	------------------------------------------	---------------------------------------

Status	Order here: https://www.hcinema.de/lampen/shop-en.php?id=fro22339 2013 Discontinued (EOL) // Last update of the data: 2023-08-04
Data	Created: 2014-09-29 12:13:47



More Details



HCinema

<https://www.projector-database.com/pro/benqts537-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.