

Dwin TransVision 4E



DWIN TRANSVISION 4E



Brief Introduction

Beta 2.5

The Dwin model TransVision 4E is a DLP projector with HDTV 1280 x 720 resolution and a contrast of 3000:1. A built-in horizontal and vertical keystone correction provides freedom when positioning the projector. An image width of up to 393 cm is possible. However, the image should be smaller in room light. We recommend max. 262 cm. The model was built by Dwin in 2005 and is no longer current.



1 x DC3 DLP Chip
HDTV 16/9 Ti Digital Light Processing Chip

Display Type

Ansi-Lumen

1500

667 Lux (bei 200 cm Screen)

Contrast

3000:1 full on/off

3000:1 full on/off

Black Level

0,5000 min. Lumen

0,223 min. Lumen

Offset

Resolution

HDTV 1280 x 720

921.600 Pixel

Video Modes

PAL, SECAM, NTSC, EDTV HDTV 720p, 1080i,

Disc Recognition

DVD | HD Blu-ray (komprimiert) | 3D-Blu-ray | 4K-UHD-Blu-ray

Application

Homecinema | Small screen width, rooms with very little ambient light below 100 lumens.

Light Source

250W VIP Lamp

Light Life

2000 h.

Operating Costs

-

Focus

Manual

Zoom

Manual 1,26

Objective

-

Throw Ratio


1,71-2,08:1

Audio

Nein

Connections

2 x DVI-D mit HDCP
2 x D-sub 15pin in
Cinch Video in
YUV in
S-Video in
RS232C
12V Trigger



16/9 screen width: 200 cm
Screen: 1 Gain

Ceiling Mounting

-

Power

300W / 5W standby

Size WxHxD

279 x 114 x 286 mm (11"x4,5"x11,3") 9,1 L/dm³

Operating Noise

-



Weight

6,35 kg / 14 lbs.

Keystone

Vert.: +/-15°

Hori.: +/-10°

Illumination

80%

Frequenz
H-sync: 15-100 kHz
V-sync: 43-120 Hz
Range max.: 230 MHz

Foot-Lamberts
62 fL / max. 393 cm screen width

212 cd/m²

- Features
- Gamma correction
 - External video processor included.
 - Carl Zeiss lens
 - 3:2 2:2 pull down De-interlacer

Screen Mirroring
-

Status
2005 Discontinued (EOL) // Last update of the data: 2025-03-03

Data



More Details



HCinema

<https://www.projector-database.com/pro/dwintransvision4e-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice.
HCinema is not responsible for any errors or omissions contained in product descriptions.