

Epson EMP 70

EPSON EMP 70



Brief Introduction

Beta 2.5

The standard portable EMP 70 LCD projector from Epson has 700 Ansi lumens, a contrast of 300:1 and an XGA 1024 x 768 resolution. The projector will be able to illuminate a picture width of 230 cm well. However, if room light is available, the image width should ideally not exceed 153 cm. The model was built by Epson in 2001 and is no longer current.

Display Type



3 x 0,7" LCD TFT Panel
XGA 4/3 Liquid Crystal Display

Ansi-Lumen

700

226 Lux (bei 203 cm Screen)

Contrast

300:1 full on/off

300:1 full on/off

Black Level

2,3333 min. Lumen

0.761 min. Lumen

Offset

-

Resolution

XGA 1024 x 768

786.432 Pixel

SXGA 1280 x 1024 compressed

Video Modes

NTSC, PAL, SECAM Pal 60 NTSC 4,43

Application

Standard-Portabel | External training and company presentations, as well as product presentations.

Small screen width, rooms with very little ambient light below 100 lumens.

Light Source

150W UHE Lamp

Articel Nr.: ELP LP13

Light Life

1500 h.

Operating Costs

-

Focus

Manual

Zoom

No Zoom

Objective

F=1,5 f=26,3mm

Throw Ratio

1,85:1

Audio

1W

Connections

Cinch Video in
Stereo Eingang
D-sub 15pin in
S Video Eingang
Maus in
Mini Jack Ein/Aus

Ceiling Mounting

-

Power

230W/ 8,6W standby

Size WxHxD

304 x 99 x 232 mm (12"x3,9"x9,1") 6,98 L/dm³

Operating Noise

-



Weight 3,10 kg / 6,83 lbs.
Keystone Vert.: +/-15°
Illumination 88%
H-sync: 15-92 kHz
Frequenz V-sync: 50-85 Hz
Range max.: 162 MHz
Foot-Lamberts 21 fL / max. 230 cm screen width
72 cd/m²


Features

- Freeze
- Kensington Slot
- Gamma correction
- Picture-in-Picture
- Remote control with mouse control

In Test -

	Bulb only	NLMP1476
	Lamp ruby	Ruby-LMP1476
Optional	Lamp original	ELPLP13 / V13H010L13
	Compatible lamp	LMP-K1476
	Universal Remote original	Fernb-uni-V3

Status Order here: <https://www.hcinema.de/lampen/shop-en.php?id=n1482>
2001 Discontinued (EOL) // Last update of the data: 2023-08-04



More Details



HCinema

<https://www.projector-database.com/pro/epsonemp70-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.