

Hitachi CP X705

HITACHI CP X705



The Hitachi CP X705 LCD projector has 4500 Ansi lumens, a contrast of 1000:1 in theater mode and an XGA 1024 x 768 resolution. The integrated lens shift gives freedom when positioning the projector. Thanks to the brightness of 4500 Ansi lumens, an image width of 584 cm is possible. The projector can also handle slightly brighter rooms with a narrower picture width (we recommend max. 389 cm). It is also Full HD 1080P compatible. The model was built by Hitachi in 2008 and is no longer current.



3 x 0,8" LCD TFT Panel
XGA 4/3 Liquid Crystal Display

Projector

4500

1000:1 full on/off im Theatre Mode

4,5000 min. Lumen

Vert.: +40% -0% Hori.: +/-10% manuell
XGA 1024 x 768

786.432 Pixel

UXGA 1600 x 1200 compressed

PAL, SECAM, NTSC, HDTV 720p, 1080i, 1080p EDTV 480p, 576p

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Wide screen width or rooms with plenty of light (over 200 lumens).

275W UHB Lamp

Articel Nr.: DT00871

2000 h. 3000 h. in Eco Mode

5,18% / 0,17 €

Manual

Manual 1,2

F=1,7-2,1 f=24,3-29,2 mm

1,5-1,8:1

4 x 4W


HDMI in
D-sub 15pin in und out
5 x BNC RGBHV in
YUV in
S-Video in
Cinch Video in
Cinch Stereo in
Mini Jack in und out
RJ45

Screen

1500 Lux (bei 200 cm Screen)

1000:1 full on/off im Theatre Mode

1,505 min. Lumen



Brief Introduction

Beta 2.5

Display Type

Ansi-Lumen

Contrast

Black Level

Lens shift

Resolution

Video Modes

Application

Light Source

Light Life

Operating Costs

Focus

Zoom

Objective

Throw Ratio

Audio

Connections

Ceiling Mounting Yes
Power 460W
Size WxHxD 420 x 139 x 319 mm (16,5"x5,5"x12,6") 18,62 L/dm³
Operating Noise 35 / 29 dB in Eco Mode

Weight 7,10 kg / 15,65 lbs.
Keystone Vert.: +/-40° automatisch
Hori.: +/-20°
Illumination -

Frequenz H-sync: 31,5-106 kHz
V-sync: 56-120 Hz

Foot-Lamberts 139 fL / max. 584 cm screen width
476 cd/m²

- Full HD 1080P compatible
- Lens shift Funktion manuell
- Freeze
- Blank (Black screen button)
- Blackboard Modus
- User logo
- Eco Mode
- Automatic and manual vertical keystone correction
- Kensington Slot
- Gamma correction
- Dynamic iris
- Password protection
- Remote control with laser pointer
- Control via web browser
- Wi-Fi network compatible.
- Lan network compatible.
- Overscan adjustable
- De-interlacer with 3:2 pull down..

Optional
Bulb only NLMP17930
Lamp ruby Ruby-LMP17930
Lamp incl. air filter original DT00871
Compatible lamp LMP-K17929
Remote original HL02881- R016F / HL03032 - R017H / HL02483
Air filter original MU03642

Order here: <https://www.hcinema.de/lampen/shop-en.php?id=n17929>

Optional Lenses

Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
UL-604	4-7.48:1	8-15 m	40%	+/-10%	Manual
SL-602	1.25-2.01:1	2.5-4 m	40%	+/-10%	Manual
LL-603	2.04-3.93:1	4.1-7.9 m	40%	+/-10%	Manual
Fix Optional Lenses					
FL-601	0.79:1	1.6 m	0.0% Fix		No Zoom

Status 2008 Discontinued (EOL) // Last update of the data: 2023-08-04
Data

More Details



H Cinema

<https://www.projector-database.com/pro/hitachicpx705-en.html>

