Hitachi CP X8160

Brief Introduction Beta 2.5	The CP X8160 LCD projector from Hitachi has 6000 ANSI lumens, a contrast ratio of 3000:1, and an XGA 1024 x 768 resolution. Files can be played directly using the integrated media player. Includes a lens shift and keystone correction function, which provides flexibility during installation. A picture width of up to 675 cm is possible; if the picture width is smaller (we recommend max. 450 cm), even rooms with residual light are no problem. Even 1080P video signals are no problem for the projector, which even has the option of projecting HD 1080P Blu-rays onto the ceiling thanks to its 360? projection. The model was built by Hitachi in 2012 and is no longer current.
Display Type	3 x 0,63" LCD TFT Panel XGA 4/3 Liquid Crystal Display
Ansi-Lumen	Projector: 6000 / 4200 im Eco Mode — Screen: 2000 Lux (bei 200 cm Screen)
Contrast	Projector: 3000:1 full on/off — Screen: 3000:1 full on/off
Black Level	Projector: 2,0000 min. Lumen — Screen: 0,667 min. Lumen
Lens shift	Vert.: +50% -0% Hori.: +/-10%
Resolution	XGA 1024 x 768 786.432 Pixel
Video Modes	PAL, SECAM, NTSC, HDTV 720p, 1080i, 1080p EDTV 480p, 576p **Media player formats:** • JPEG (.jpeg, .JPEG) • Bitmap (.bmp) • PNG (.png) • GIF (.gif) • Movie (.avi, .mov)
Application	Stationary | Permanent installation in the training room and meeting room as well as the conference room. Very large screen width and rooms with plenty of light and shaded daylight.
Light Source	330W UHP Lamp Article Nr.: DT01291
Light Life	2500 h. 3000 in Eco Mode
Operating Costs	4,03% / 0,14 €
Focus	Powered
Zoom	Powered 1,47
Objective	-
Throw Ratio	1,5-2,2:1
Audio	2 x 8W
Connections	2 x HDMI in 5 x BNC RGBHV in 2 x D-sub 15 pin in S-Video in



HITACHI CP X8160

	Cinch Video in Cinch Stereo in USB Typ A,B in Mini Jack Audio in und out RS232C Din 9 pin RJ45 in
Ceiling Mounting	Yes, is possible.
Power	-
Size WxHxD	498 x 135 x 396 mm (19,6"x5,3"x15,6") 26,62 L/dm³
Operating Noise	38,5 / 29 dB in Eco Mode
Weight	8,30 kg / 18,3 lbs.
Keystone	Vert.: +/-35° automatisch
Illumination	-
Frequenz	-
Foot-Lamberts	186 fL / max. 675 cm screen width 637 cd/m²
Features	■ Full HD 1080P compatible ■ Lens shift Funktion ■ Integrated Mediaplayer ■ Freeze ■ Blackboard Modus ■ User logo ■ Eco Mode ■ Automatic and manual vertical keystone correction ■ Kensington Slot ■ Digital image shift ■ 360° installable ■ Password protection ■ PJLink™ ■ Optional Wi-Fi network compatible. ■ Lan network compatible. ■ Crestron®-Software compatible. ■ Picture side by picture ■ DICOM support.
Screen Mirroring	-



Optional accessories

	Nackte Philips Lampe	NLMP20885	124,56 €
	Lampe Ruby	Ruby-LMP20885	173,68 €
	Lampe Original	DT01291	361,71 €
	Kompatible Lampe	LMP-K20884	78,69 €
	Luftfilter Kompatibel	Alternative zu:UX38241 / MU06642	31,24 €
	Objektiv Original	SL-702	EOL €
	Objektiv Original	ML-703	EOL €
	Objektiv Original	LL-704	EOL €
	Objektiv Original	FL-701	EOL €

	Universal Fernbedienung	Fernb-uni-V3	22,31 €
	Fernbedienung Original	HL02801 / R100	79,54 €
	Luftfilter Original	UX38241	56,67 €
	Deckenhalterung 100-120	Halterung100	47,86 €

Optional Lenses

Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
SL-702	1.2-1.8:1	2.4-3.6 m	40%	+/-10%	Powered
ML-703	1.5-3:1	3-6 m	50%	+/-10%	Powered
LL-704	2.5-5:1	5-10 m	40%	+/-10%	Powered
Fix Optional Lenses					
FL-701	0.8:1	1.6 m	0.0% Fix		No Zoom

Status 2012 Discontinued (EOL) // Last update of the data: 2023-08-04

Data

More Details

HCinema

https://www.projector-database.com/pro/hitachicpx8160-en.html

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.