

Optoma EzPro / EP756

OPTOMA EZPRO / EP756



Brief Introduction

Beta 2.5

The EzPro / EP756 DLP has 2000 Ansi lumens, a contrast of 2000:1 and an XGA 1024 x 768 resolution. Due to the brightness of 2000 Ansi lumens, a picture width of 389 cm is possible. In room light, the picture should be max. 259 cm wide. The model was built by Optoma in 2003 and is no longer current.

Display Type



1 x 0,7" DDR DLP
XGA 4/3 Ti Digital Light Processing Chip

Ansi-Lumen

2000 647 Lux (bei 203 cm Screen)

Contrast

2000:1 full on/off 2000:1 full on/off

Black Level

1,0000 min. Lumen 0.324 min. Lumen

Offset

Resolution

XGA 1024 x 768

786.432 Pixel

Video Modes

SXGA 1280x1024 compressed

Pal, Pal-M, Pal-N, SECAM, NTSC, HDTV 720p, 1080i,

Application

Standard-Portabel | External training and company presentations, as well as product presentations.

Medium screen width or rooms with little light, max. 100 lumens.

Light Source

250W UHP Lamp

Articel Nr.: SP.86501.001 /

SP.L1501.001

Light Life

2000 h.

Operating Costs

23,81% / 0,1 €

Focus

Manual

Zoom

Manual 1,2

Objective

F=2,44-2,69 f=28,8-34,5 mm

Throw Ratio

2,0-2,4:1

Audio

2 x 3W Stereo

Connections

D-sub 15pin in und out

DVI-I


Cinch Video in

S-Video in

3 x Mini Jack in 1 x out

RS232C

Maus Port





Ceiling Mounting
Power
Size WxHxD
Operating Noise

Yes
360W Max
277 x 85 x 225 mm (10,9"x3,3"x8,9") 5,3 L/dm³
32dB

Weight
Keystone
Illumination

2,90 kg / 6,39 lbs.
Vert.: +/-16°
80%

Frequenz

H-sync: 15-100 kHz
V-sync: 43-120 Hz

Foot-Lamberts

60 fL / max. 389 cm screen width
206 cd/m²

Features

- Freeze
- Kensington Slot
- Picture-in-Picture
- Remote control with laser pointer und mouse control
- Digital Zoom
- Silicon Image Si504 De-Interlacer with 2:3 2:2 pull down


Optional

- | | |
|---------------------------|--------------------------|
| Osram bulb only | NLMP15521 |
| Lamp ruby | Ruby-LMP15521 |
| Lamp original | BL-FU250A / SP.86501.001 |
| Universal Remote original | Fernb-uni-V3 |

Status

Order here: <https://www.hcinema.de/lampen/shop-en.php?id=n2636>
2003 Discontinued (EOL) // Last update of the data: 2023-08-04

Data



More Details



HCinema

<https://www.projector-database.com/pro/optomaep756-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.