


Panasonic PT DW750/L

PANASONIC PT DW750/L



The stationary PT DW750/L DLP has 7000 Ansi lumens, a contrast of 3000:1 and a WXGA 1280 x 800 resolution. The lamp life is specified by the manufacturer as 4000 hours, which is over 5.5 years if enjoyed for two hours a day. Includes a lens shift and keystone correction function, which provides freedom during installation. The projector can illuminate images up to 850 cm wide thanks to its 7000 Ansi lumens. The projector can create rooms with residual light with a smaller image width, we recommend a maximum of 567 cm. If the image is still too small, the integrated edge blending software can help to project a larger image with additional projectors. Even 1080P playback is no problem for the projector. With only 30 decibels of operating noise, the model is already very quiet compared to others. The model was built by Panasonic in 2015 and is no longer current.



1 x 0,65" DLP Chip
WXGA 16/10 Ti Digital Light Processing Chip

Brief Introduction

Beta 2.5

Display Type

Ansi-Lumen

Contrast

Black Level

Lens shift

Resolution

Video Modes

Application

Light Source

Light Life

Operating Costs

Focus

Zoom

Objective

Throw Ratio

Audio

Projector

7000

3000:1 full on/off

2,3333 min. Lumen

Vert.: +60% -16% Hori.: +10% -30%

WXGA 1280 x 800

1.024.000 Pixel

Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p EDTV 480p, 576p

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Very large screen width and rooms with plenty of light and shaded daylight.

2 x 310W Lamp

Article Nr.: ET-LAD70W

4000 h.

4% / 0,14 €

Powered

Powered 1,39

L / optional

1,8-2,5:1


Nein

Screen

2800 Lux (bei 200 cm Screen)


3000:1 full on/off

0,934 min. Lumen



Connections	HDMI in
	DVI-D
	D-Sub 15 pin in
	5 x BNC RGBHV in
	Video BNC in
	S-Video in
	RS232C Din 9 pin in und out
	Mini jack Remote in und out
	RJ458 in
	SDI über BNC in
Ceiling Mounting	Yes, is possible.
Power	-
Size WxHxD	498 x 175 x 521 mm (19,6"x6,9"x20,5") 45,41 L/dm³
Operating Noise	30 / 28 dB in Eco Mode

Weight	17,60 kg / 38,8 lbs.
Keystone	Vert.: +/-40° Hori.: +/-15°
Illumination	90%
Frequenz	H-sync: 15-100 kHz V-sync: 24-120 Hz Range max.: 162 MHz
Foot-Lamberts	260 fL / max. 850 cm screen width 891 cd/m²
Features	■ Full HD 1080P compatible
	■ Lens shift Funktion
	■ Eco Mode
	■ Kensington Slot
	■ Warping
	■ 24/7 continuous operation capable
	■ Edge Blending
	■ Lan network compatible.
	■ Liquid-cooled system
	■ Daylight View 2
Screen Mirroring	■ Detail Clarity Processor
	■ Dynamic RGB Booster
	■ Art-Net DMX compatible
	-




Optional accessories

	Doppel Lampe Ruby	Ruby-LMP23290	363,02 €
	Einzel Lampe Ruby	Ruby-LMP23288	176,58 €
	Doppel Lampe inkl. Luftfilter Original	ET-LAD70W / ET-LAD70AW	578,04 €
	Einzel Lampe inkl. Luftfilter Original	ET-LAD70	444,76 €
	Doppel Kompatible Lampe	LMP-K23289	159,50 €
	Einzel Kompatible Lampe	LMP-K23286	82,87 €
	Objektiv Original	ET-DLE150	3.481,37 €
	Objektiv Original	ET-DLE060	4.005,06 €
	Objektiv Original	ET-DLE105	5.215,56 €
	Deckenhalterung Original	ET-PKD130B	EOL €
	Deckenhalterung Original	ET-PKD120S	EOL €
	Deckenhalterung Original	ET-PKD120H	EOL €

	Objektiv Gebraucht Original	ET-DLE250	1.898,73 €
	Objektiv Gebraucht Original	ET-DLE150Z	1.839,23 €
	Objektiv Gebraucht Original	ET-DLE450	1.482,23 €
	Objektiv Gebraucht Original	ET-DLE350	3.481,37 €
	Objektiv Gebraucht Original	ET-DLE030	4.363,33 €
	Objektiv Original	ET-DLE055	4.151,99 €
	Objektiv Gebraucht Original	ET-DLE085	2.811,38 €
	Fernbedienung Original	N2QAYA000060	30,40 €
	Filter Original	TMZX5229-1	22,91 €
	Deckenhalterung 220	Halterung45	83,60 €

Status

2015 Discontinued (EOL) // Last update of the data: 2025-03-03
Created: 2015-02-10 15:26:31



More Details



HCinema

<https://www.projector-database.com/pro/panasonicptdw750-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice.
HCinema is not responsible for any errors or omissions contained in product descriptions.