

Panasonic PT-RZ770 E/U/B/W

PANASONIC PT-RZ770 E/U/B/W



A brief introduction to the PT-RZ770 E/U/B/W: The Panasonic laser DLP projector offers 7000 Ansi lumens, a contrast of 10000:1 and a WUXGA 1920 x 1200 resolution. The lifespan of the laser is 20000 hours, which is over 13.7 years with a daily viewing time of 4 hours. Including a lens shift and keystone correction function, which provides freedom during installation. Thanks to the brightness of 7000 Ansi lumens, a picture width of 850 cm is possible. The projector can also handle slightly brighter rooms with a smaller picture width (we recommend max. 567 cm). If the image width is not sufficient, the projector offers integrated edge blending software, which allows several projectors to project a large image together. Even 1080P video signals are no problem for the projector. Even projection onto the ceiling is possible thanks to the 360° projection. The model was built by Panasonic in 2016 and is no longer current.

Brief Introduction Beta 2.5



1 x 0,67" DLP Chip
WUXGA 16/9 Ti Digital Light Processing Chip

Display Type

Ansi-Lumen

Contrast

Black Level

Lens shift

Resolution

Video Modes

Application

Light Source

Light Life

Operating Costs

Focus

Zoom

Objective

Throw Ratio

Audio

Projector

7000

10000:1 full on/off

0,7000 min. Lumen

Vert.: +50% -16% Hori.: +30% -10%

WUXGA 1920 x 1200

2.304.000 Pixel

Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p EDTV 480p, 576p

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Very large screen width and rooms with plenty of light and shaded daylight.

Laserdiode

Article Nr.: N2QAYA000060

20000 h.

0,00 € Laser

Powered

Powered 1,41

F=1,7-1,9 f=25,6-35,7 mm

1,7-2,4:1


Nein

Screen

3111 Lux (bei 200 cm Screen)

10000:1 full on/off

0,311 min. Lumen



Connections	HDMI in DVI-D in D-sub 15pin in 5 x BNC RGBHV in RS232C Din 9 pin in RJ45 in SDI IN BNC x 1 (3G/HD/SD-SDI) DIGITAL LINK
Ceiling Mounting	Yes, is possible.
Power	-
Size WxHxD	498 x 200 x 538 mm (19,6"x7,9"x21,2") 53,58 L/dm³
Operating Noise	35dB

Weight 22,70 kg / 50,04 lbs.

Keystone Vert.: +/-40°


Illumination Hori.: +/-15°

Frequenz 90%
H-sync: 15-100 kHz
V-sync: 24-120 Hz

Foot-Lamberts 289 fL / max. 850 cm screen width
990 cd/m²

- Full HD 1080P compatible
- Lens shift Funktion
- Eco Mode
- 360° installable
- 24/7 continuous operation capable
- Edge Blending
- PJLink™
- Lan network compatible.
- Picture-in-picture
- DICOM simulation

Screen Mirroring -



Optional accessories

	Objektiv Original	ET-DLE150	3.481,37 €
	Objektiv Original	ET-DLE060	4.005,06 €
	Deckenhalterung Original	ET-PKD130B	EOL €
	Deckenhalterung Original	ET-PKD120S	EOL €
	Deckenhalterung Original	ET-PKD120H	EOL €
	Objektiv Gebraucht Original	ET-DLE250	1.898,73 €
	Objektiv Gebraucht Original	ET-DLE150Z	1.839,23 €
	Objektiv Gebraucht Original	ET-DLE450	1.482,23 €
	Objektiv Gebraucht Original	ET-DLE350	3.481,37 €
	Objektiv Gebraucht Original	ET-DLE030	4.363,33 €
	Objektiv Original	ET-DLE055	4.151,99 €
	Objektiv Gebraucht Original	ET-DLE085	2.811,38 €
	Fernbedienung Original	N2QAYA000060	30,40 €
	Deckenhalterung Länge 225 mm	Halterung45	85,80 €

Optional Lenses					
Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
ET-DLE450	5.6-9:1	11.2-18 m	50-16%	30-10%	Powered
ET-DLE350	3.6-5.4:1	7.2-10.8 m	50-16%	30-10%	Powered
ET-DLE250	2.3-3.6:1	4.6-7.2 m	50-16%	30-10%	Powered
ET-DLE150	1.3-1.9:1	2.6-3.8 m	50-16%	30-10%	Powered
ET-DLE085	0.8-1:1	1.6-2 m	50-16%	28-10%	Powered
ET-DLE060	0.6-0.8:1	1.2-1.6 m	0.00% Fix		Powered
Fix Optional Lenses					
ET-DLE055	0.8:1	1.6 m	0.00% Fix		No Zoom
ET-DLE030	0.38:1	0.8 m			No Zoom
Status	2016 Discontinued (EOL) // Last update of the data: 2025-03-03 Created: 2016-06-21 14:15:35				



More Details

HCinema

<https://www.projector-database.com/pro/panasonicptrz770-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice.
HCinema is not responsible for any errors or omissions contained in product descriptions.