

Sony SRX S105

SONY SRX S105



With the SRX S105, manufacturer Sony offers a stationary SXR projector with UHD (4K+2K) 4096 x 2160 resolution and a contrast of 1800:1. The integrated lens shift gives you freedom when positioning the projector. The projector can illuminate a screen width of up to 813 cm thanks to its 5000 Ansi lumens. The projector can create rooms with residual light with a smaller image width, we recommend a maximum of 542 cm. Playing 1080P and 4K is also no problem for the projector. The model was built by Sony in 2006 and is no longer current.

Brief Introduction

Beta 2.5

Display Type

3 x 1,55" SXR Panel
UHD 19/10 Silicon X-tal Reflective Display (SXR)

Ansi-Lumen

5000

2370 Lux (bei 200 cm Screen)

Contrast

1800:1 full on/off

1800:1 full on/off

Black Level

2,7778 min. Lumen

1,318 min. Lumen

Lens shift

Vert.: +/-50%

Resolution

UHD (4K+2K) 4096 x 2160
8.847.360 Pixel

Video Modes

Pal, SECAM, NTSC, HDTV 720p, 1080i, 1080p, 4K UHD, EDTV 480p, 576p

Application

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Wide screen width or rooms with plenty of light (over 200 lumens).

Light Source

2 x 1000W Xenon Lamp

Light Life

Article Nr.: LKRX-B105 / LKRX-105

1000 h.

Operating Costs

-

Focus

Powered

Zoom

Powered

Objective

optional

Throw Ratio

optional

Audio

Nein

Connections

DVI-Input Card (LKRI-004)

5 x BNC RGBHV in

RJ45

RS232C Din 9pin in

weitere optional

Ceiling Mounting


Yes, is possible.

Power

3000W

Size WxHxD

740 x 500 x 1330 mm (29,1"x19,7"x52,4") 492,1 L/dm³



Operating Noise 65dB

Weight 85,00 kg / 187,39 lbs.

Keystone -

Illumination -


Frequenz -

Foot-Lamberts 220 fL / max. 813 cm screen width
754 cd/m²

Features

- Full HD 1080P compatible
- Lens shift Funktion
- Gamma correction
- 24/7 continuous operation capable
- Lan network compatible.

Screen Mirroring -



Optional accessories

	Nackte Lampe Original	LKRX-105	EOL €
	Lampe Original	LKRX-B105	EOL €

Optional Lenses

Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
LKRL-Z140	3.86-7.06:1	7.7-14.1 m	+/-50%		Powered
LKRL-Z125	2.36-3.88:1	4.7-7.8 m	+/-50%		Powered
Sony LKRL-Z122	2.23-3.92:1	4.5-7.8 m	+/-50%		Powered
LKRL-Z120	1.71-2.25:1	3.4-4.5 m	+/-50%		Powered
Sony LKRL-Z117	1.73-2.41:1	3.5-4.8 m	+/-50%		Powered
LKRL-Z115	1.46-1.72:1	2.9-3.4 m	+/-50%		Powered

Fix Optional Lenses

Sony LKRL-90	0.86:1	1.7 m	+/-15%		No Zoom
--------------	--------	-------	--------	--	---------

Status 2006 Discontinued (EOL) // Last update of the data: 2025-03-03

Data



More Details



HCinema

<https://www.projector-database.com/pro/sonysrxs105-en.html>

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.