


Vivitek D5500



VIVITEK D5500



Brief Introduction

Beta 2.5

A brief introduction to the D5500: The Vivitek BrilliantColor DLP projector offers 5500 Ansi lumens, a contrast of 2500:1 and an XGA 1024 x 768 resolution. With the lens shift function, the projector can be positioned very freely. An image width of up to 646 cm is possible, if the image width is smaller (we recommend max. 431 cm), rooms with residual light are also no problem. The model was built by Vivitek in 2008 and is no longer current.

Display Type



1 x 0,7" DLP Chip
XGA 4/3 Ti Digital Light Processing Chip

Ansi-Lumen

Projector 5500

Screen 1833 Lux (bei 200 cm Screen)

Contrast

2500:1 full on/off

Screen 2500:1 full on/off

Black Level

2,2000 min. Lumen

Screen 0,734 min. Lumen

Lens shift

Vert.: +50% -0% Hori.: +/-10%

Resolution

XGA 1024 x 768

786.432 Pixel

Video Modes

UXGA 1600 x 1200 compressed

Application

PAL, SECAM, NTSC, HDTV 720p, 1080i, EDTV 480p, 576p

Stationary | Permanent installation in the training room and meeting room as well as the conference room.

Wide screen width or rooms with plenty of light (over 200 lumens).

Light Source

2 x 260W Lamp

Articel Nr.: 5811100560-S

Light Life

2000 h.

Operating Costs

11,89% / 0,39 €

Focus

Powered

Zoom

Powered 1,32

Objective

optional

Throw Ratio

optional

Audio

2 x 3W Stereo

Connections

DVI-D mit HDCP in

D-sub 15 pin in und out

YUV in

S-Video in


Cinch Video in

RS232C

USB Typ B in

RJ45 in

Mini Jack Audio in und out





Ceiling Mounting
Power
Size WxHxD
Operating Noise

-
655 / 580W in Eco Mode
505 x 192,10 x 385 mm (19,9"x7,6"x15,2") 37,33 L/dm³
35 / 32 dB in Eco Mode

Weight
Keystone
Illumination
Frequenz
Foot-Lamberts

20,50 kg / 44,09 lbs.
Vert.: +/-40°
Hori.: +/-35°
90%
H-sync: 15-94 kHz
V-sync: 50-85 Hz
170 fL / max. 646 cm screen width
582 cd/m²


Features

- Direkt Power Off
- Lens shift Funktion
- Freeze
- Blank (Black screen button)
- Eco Mode
- Kensington Slot
- Gamma correction
- Password protection
- BrilliantColor™
- PJLink™
- Control via web browser
- Lan network compatible.
- Overscan adjustable
- .

Optional

Bulb only	NLMP20200
Lamp ruby	Ruby-LMP20200
Lamp original	5811100560-S
Compatible lamp	LMP-K19141
Remote control original	5041841300

Order here: <https://www.hcinema.de/lampen/shop-en.php?id=n19141>



Optional Lenses					
Name	Ratio	Distance	Shift V	Shift H	Zoom
Zoom Optional Lenses					
4.43-8.3:1	4.43-8.3:1	8.9-16.6 m	50%	+/-10%	Powered
2.22-4.43:1	2.22-4.43:1	4.4-8.9 m	50%	+/-10%	Powered
1.78-2.35:1	1.78-2.35:1	3.6-4.7 m	50%	+/-10%	Powered
1.33-1.79:1	1.33-1.79:1	2.7-3.6 m	50%	+/-10%	Powered
Fix Optional Lenses					
0.77:1	0.77:1	1.5 m	0.0% Fix		No Zoom
Status Data	2008 Discontinued (EOL) // Last update of the data: 2023-08-23				



HCinema

<https://www.projector-database.com/pro/vivitekD5500-en.html>

More Details

Due to our ongoing commitment to continuously improve the quality of our projector database, this brochure is also subject to change without notice. HCinema is not responsible for any errors or omissions contained in product descriptions.